

Specifications



Photo is representative



Eaton 197905

Eaton Moeller® series DILH Contactor, Ith = Ie: 850 A, RA 250: 110 - 250 V 40 - 60 Hz/110 - 350 V DC, AC and DC operation, Screw connection

General specifications

PRODUCT NAME	Eaton Moeller® series DILH contactor
CATALOG NUMBER	197905
MODEL CODE	DILH600/22(RA250)
EAN	4015081954247
PRODUCT LENGTH/DEPTH	216 mm
PRODUCT HEIGHT	237 mm
PRODUCT WIDTH	160 mm
PRODUCT WEIGHT	8.85 kg

CERTIFICATIONS

CSA Class No.: 3211-04
UL File No.: E29096
UL Category Control No.: NLDX
IEC/EN 60947-4-1
UL 60947-4-1
CE marking
VDE 0660
UL/CSA
CSA file No. 012528
North America (UL listed, CSA certified)
EN 45545: Fire protection on railway vehicles
IEC 61373: Vibration and shock, tested for category 1 class B

CATALOG NOTES

- Contacts according to EN 50012
- EN 45545 - Fire protection on railway vehicles: Fire protection class of all plastics according to UL94: V-0 / plastic weight in total: 2.576 kg
- For rated



Powering Business Worldwide

AC-1/Conventional thermal current Ith

**CONVENTIONAL
THERMAL CURRENT ITH
(3-POLE, ENCLOSED)** 600 A

**CONVENTIONAL
THERMAL CURRENT ITH
AT 40°C (3-POLE, OPEN)** 850 A

**CONVENTIONAL
THERMAL CURRENT ITH
AT 50°C (3-POLE, OPEN)** 760 A

**CONVENTIONAL
THERMAL CURRENT ITH
AT 55°C (3-POLE, OPEN)** 725 A

**CONVENTIONAL
THERMAL CURRENT ITH
AT 60°C (3-POLE, OPEN)** 695 A

**CONVENTIONAL
THERMAL CURRENT ITH
OF MAIN CONTACTS (1-
POLE, OPEN)** 1738 A

Contacts

**NUMBER OF AUXILIARY
CONTACTS (NORMALLY
CLOSED CONTACTS)** 2

**NUMBER OF AUXILIARY
CONTACTS (NORMALLY
OPEN CONTACTS)** 2

operational voltage
above 800 V AC
additional phase
separators
DILH800-XKP have
to be used

- Conventional
thermal current Ith
of main contacts (1-
pole, open) at 60°

Climatic environmental conditions

ALTITUDE Max. 2000 m

**AMBIENT OPERATING
TEMPERATURE - MAX** 70 °C

**AMBIENT STORAGE
TEMPERATURE - MAX** 80 °C

**AMBIENT OPERATING
TEMPERATURE - MIN** -40 °C

**AMBIENT STORAGE
TEMPERATURE - MIN** -40 °C

CLIMATIC PROOFING Damp heat, cyclic, to IEC
60068-2-30
Damp heat, constant, to
IEC 60068-2-78

Design verification

10.10 TEMPERATURE RISE

The panel builder is
responsible for the
temperature rise
calculation. Eaton will
provide heat dissipation
data for the devices.

10.11 SHORT-CIRCUIT RATING

Is the panel builder's
responsibility. The
specifications for the
switchgear must be
observed.

10.12 ELECTROMAGNETIC COMPATIBILITY

Is the panel builder's
responsibility. The
specifications for the
switchgear must be
observed.

10.13 MECHANICAL FUNCTION

The device meets the
requirements, provided
the information in the

	instruction leaflet (IL) is observed.
10.2.2 CORROSION RESISTANCE	Meets the product standard's requirements.
10.2.3.1 VERIFICATION OF THERMAL STABILITY OF ENCLOSURES	Meets the product standard's requirements.
10.2.3.2 VERIFICATION OF RESISTANCE OF INSULATING MATERIALS TO NORMAL HEAT	Meets the product standard's requirements.
10.2.3.3 RESIST. OF INSUL. MAT. TO ABNORMAL HEAT/FIRE BY INTERNAL ELECT. EFFECTS	Meets the product standard's requirements.
10.2.4 RESISTANCE TO ULTRA-VIOLET (UV) RADIATION	Meets the product standard's requirements.
10.2.5 LIFTING	Does not apply, since the entire switchgear needs to be evaluated.
10.2.6 MECHANICAL IMPACT	Does not apply, since the entire switchgear needs to be evaluated.
10.2.7 INSCRIPTIONS	Meets the product standard's requirements.
10.3 DEGREE OF PROTECTION OF ASSEMBLIES	Does not apply, since the entire switchgear needs to be evaluated.
10.4 CLEARANCES AND CREEPAGE DISTANCES	Meets the product standard's requirements.
10.5 PROTECTION AGAINST ELECTRIC SHOCK	Does not apply, since the entire switchgear needs to be evaluated.
10.6 INCORPORATION OF SWITCHING DEVICES AND COMPONENTS	Does not apply, since the entire switchgear needs to be evaluated.
10.7 INTERNAL ELECTRICAL CIRCUITS AND CONNECTIONS	Is the panel builder's responsibility.
10.8 CONNECTIONS FOR EXTERNAL CONDUCTORS	Is the panel builder's responsibility.
10.9.2 POWER-FREQUENCY ELECTRIC STRENGTH	Is the panel builder's responsibility.
10.9.3 IMPULSE WITHSTAND VOLTAGE	Is the panel builder's responsibility.
10.9.4 TESTING OF ENCLOSURES MADE OF INSULATING MATERIAL	Is the panel builder's responsibility.
EQUIPMENT HEAT	0 W

DISSIPATION, CURRENT-DEPENDENT PVID

HEAT DISSIPATION CAPACITY PDISS 0 W

RATED OPERATIONAL CURRENT FOR SPECIFIED HEAT DISSIPATION (IN) 650 A

STATIC HEAT DISSIPATION, NON-CURRENT-DEPENDENT PVS 7.9 W

Electrical rating

RATED BREAKING CAPACITY AT 1000 V 1575 A

RATED BREAKING CAPACITY AT 220/230 V 4800 A

RATED BREAKING CAPACITY AT 380/400 V 4800 A

RATED BREAKING CAPACITY AT 500 V 4800 A

RATED BREAKING CAPACITY AT 660/690 V 2000 A

RATED INSULATION VOLTAGE (UI) 1000 V

RATED MAKING CAPACITY UP TO 440 V (COS PHI TO IEC/EN 60947) 6000 A

RATED OPERATIONAL VOLTAGE (UE) AT AC - MAX 1000 V

SAFE ISOLATION 1000 V AC, Between coil and contacts, According to EN 61140

General information

ACCESSORIES Fitting options auxiliary contacts: on the side: 2 x DILM820-XHI11(V)-SI; 2 x DILM820-XHI11-SA

APPLICATION Mains contactors for resistive loads from 1000 A

CONNECTION Screw terminals

DEGREE OF PROTECTION IP00

ELECTROMAGNETIC COMPATIBILITY Designed for operation in industrial environments. Its use in residential environments may cause radio-frequency interference, requiring additional noise suppression.

FITTED WITH: Suppressor circuit in actuating electronics

LIFESPAN, MECHANICAL 3,000,000 Operations (AC operated)
3,000,000 Operations (DC operated)

OPERATING FREQUENCY 1000 mechanical Operations/h (AC operated)
1000 mechanical Operations/h (DC operated)

OVERVOLTAGE CATEGORY III

POLLUTION DEGREE 3

PRODUCT CATEGORY Contactors

RATED IMPULSE WITHSTAND VOLTAGE (UIMP) 12000 V

RESISTANCE 500 mΩ (Admissible transitional contact resistance - of the external

	control circuit device when actuating A11)
SHOCK RESISTANCE	10 g, N/O auxiliary contact, Mechanical, according to IEC/EN 60068-2-27, Half-sinusoidal shock 10 ms 8 g, N/C auxiliary contact, Mechanical, according to IEC/EN 60068-2-27, Half-sinusoidal shock 10 ms 10 g, N/O main contact, Mechanical, according to IEC/EN 60068-2-27, Half-sinusoidal shock 10 ms
SIGNAL LEVEL	5 V - 15 V, PLC signal level (A3 - A4) to IEC/EN 61131-2 (type 2), Magnet systems
UTILIZATION CATEGORY	AC-1: Non-inductive or slightly inductive loads, resistance furnaces
VOLTAGE TYPE	AC/DC

Magnet system

BEHAVIOR IN MARGINAL AND TRANSITIONAL CONDITIONS

Sealing - Voltage interruptions 0 - 0.2 x U_c min) > 10 ms: Drop-out of the contactor
 Sealing - Voltage drops (0.6 - 0.7 x U_c min: Contactor remains switched on
 Sealing - Voltage interruptions (0 - 0.2 x U_c min $\leq$ 10 ms: Time is bridged specifically
 Sealing - Voltage drops (0.2 - 0.6 x U_c min) > 12 ms: Drop-out of the contactor
 Sealing - Pick-up phase (0.7 x U_c min - 1.15 x U_c max): Contactor switches on properly
 Sealing - Voltage drops (0.2 - 0.6 x U_c min $\leq$ 12 ms: Time is bridged specifically

Sealing - Excess voltage (1.15 - 1.3 x U_c max): Contactor remains switched on
 Sealing - Pick-up phase (0 - 0.7 x U_c min: Contactor does not switch on

DROP-OUT VOLTAGE

AC operated: 0.2 x U_S max - 0.6 x U_S min, AC operated
 DC operated: 0.2 x U_S max - 0.6 U_S min, DC operated

DUTY FACTOR

100 %

PICK-UP VOLTAGE

0.7 - 1.15 V DC x U_S
 0.7 - 1.15 V AC x U_S

POWER CONSUMPTION

Control transformer with $u_k \leq 7\%$

POWER CONSUMPTION, PICK-UP, 50 HZ

495 VA, Pull-in power, Coil in a cold state and 1.0 x U_S

POWER CONSUMPTION, PICK-UP, 60 HZ

495 VA, Pull-in power, Coil in a cold state and 1.0 x U_S

POWER CONSUMPTION, SEALING, 50 HZ

3.3 W, Coil in a cold state and 1.0 x U_S

POWER CONSUMPTION, SEALING, 60 HZ

3.3 W, Coil in a cold state and 1.0 x U_S

RATED CONTROL SUPPLY VOLTAGE (US) AT AC, 50 HZ - MAX

250 V

RATED CONTROL SUPPLY VOLTAGE (US) AT AC, 50

110 V

Switching capacity

SWITCHING CAPACITY (AUXILIARY CONTACTS, GENERAL USE)

10 A, 600 V AC, (UL/CSA)
 1 A, 250 V DC, (UL/CSA)

SWITCHING CAPACITY (AUXILIARY CONTACTS, PILOT DUTY)

P300, DC operated (UL/CSA)
 A600, AC operated (UL/CSA)

SWITCHING CAPACITY (MAIN CONTACTS, GENERAL USE)

700 A, Maximum motor rating (UL/CSA)

HZ - MIN	
RATED CONTROL SUPPLY VOLTAGE (US) AT AC, 60 HZ - MAX	250 V
RATED CONTROL SUPPLY VOLTAGE (US) AT AC, 60 HZ - MIN	110 V
RATED CONTROL SUPPLY VOLTAGE (US) AT DC - MAX	350 V
RATED CONTROL SUPPLY VOLTAGE (US) AT DC - MIN	110 V
SWITCHING TIME (AC OPERATED, MAKE CONTACTS, CLOSING DELAY) - MAX	60 ms
SWITCHING TIME (AC OPERATED, MAKE CONTACTS, OPENING DELAY) - MAX	50 ms

Terminal capacities

SCREW SIZE	M3.5, Terminal screw M10, Terminal screw
SCREWDRIVER SIZE	2, Terminal screw, Pozidriv screwdriver 0.8 x 5.5/1 x 6 mm, Terminal screw, Control circuit cables, Standard screwdriver
STRIPPING LENGTH (CONTROL CIRCUIT CABLE)	10 mm
TERMINAL CAPACITY (BUSBAR)	50 mm width, Main connection
TERMINAL CAPACITY (FLEXIBLE WITH CABLE LUG)	50 - 240 mm ²
TERMINAL CAPACITY (FLEXIBLE WITH FERRULE)	1 x (0.75 - 2.5) mm ² 2 x (0.75 - 2.5) mm ²
TERMINAL CAPACITY (SOLID)	1 x (0.75 - 2.5) mm ² 2 x (0.75 - 2.5) mm ²
TERMINAL CAPACITY (SOLID/STRANDED AWG)	18 - 14
TERMINAL CAPACITY (STRANDED WITH CABLE LUG)	70 - 240 mm ²
TIGHTENING TORQUE	1.2 Nm, Screw terminals 24 Nm, Main cable connection screw/bolt
WIDTH ACROSS FLATS	16 mm

Resources

BROCHURES	eaton-product-brochure-dilmilh-power-contactors-brochure-br034010en-en-us.pdf
CHARACTERISTIC CURVE	eaton-contactors-short-time-loading-dilm-characteristic-curve-002.eps eaton-contactors-dilh-characteristic-curve.eps eaton-contactors-characteristic-curve-2110dia-4.eps
DECLARATIONS OF CONFORMITY	eaton-contactor-declaration-of-conformity-uk251104en.pdf eaton-contactor-declaration-of-conformity-eu250621en.pdf
DRAWINGS	eaton-contactors-mounting-dilm-dimensions.eps eaton-contactors-mounting-dilm-dimensions-002.eps eaton-contactors-dimensions-006.eps eaton-contactors-mounting-dilm-3d-drawing-002.eps
ECAD MODEL	DA-CE-ETN.DILH600 22(RA250)
INSTALLATION INSTRUCTIONS	eaton-contactors-dilm-dilh-sond735-il034115zu.pdf eaton-contactors-dilh600-dilh800-il034082zu.pdf
MCAD MODEL	eaton-iec-contactors-mcad-3d-models-dilh600-800-S22.stp eaton-iec-contactors-mcad-drawings-dilh600-800-S22.dwg
WIRING DIAGRAMS	eaton-contactors-contact-dilm-wiring-diagram-004.eps

PROJECT NAME:
PROJECT NUMBER:
PREPARED BY:
DATE:



Eaton Corporation plc Eaton House
30 Pembroke Road
Dublin 4, Ireland
Eaton.com

© 2026 Eaton. All Rights Reserved.

Follow us on social media to get the latest product and support information.

